

WIS 164, Rehabilitation Project

CTH Q to CTH E
Washington County

Fall 2018

Business and Resident Meeting

Project Overview:

The \$13,262,826 project has been awarded to Mashuda Contractors, Inc. out of Princeton Wisconsin. The Wisconsin Department of Transportation (WisDOT) will rehabilitate WIS 164 from 1000 ft. north of CTY Q to 3300 ft. north of CTY E. Project Scope:

Resurface existing pavement with 5 spot improvements to address steep hills and sight distance

- Replace pavement marking and signage
- Increase lane width by 1' (12' lane) and shoulder width by 2' (10' shoulder, 6' paved)
- Flatten side slopes adjacent to shoulder
- On-street bike accommodations provided with a 6' paved shoulder
- Upgrade intersections to current design standards – add turn lanes and bypass lanes

5 Spot Improvements include:

- Shady Lane and WIS 164 Intersection
 - Extend Shady Lane to Hansen Drive, cul de sac the south end
 - WIS 164 will be reconstructed to flatten roadway grades and improve sight distances
- WIS 164 will be reconstructed to flatten roadway grades and improve sight distances just north of Monches Road
- WIS 164 will be reconstructed to flatten roadway grades and improve sight distances just north of just south of Hubertus Road
- Single lane Roundabout at WIS 167
- WIS 164 will also be reconstructed to flatten roadway grades and improve sight distances just south of WIS 167
 - Pleasant Hill Road and WIS 164 Intersection

Schedule/Traffic Impacts:

2018

STAGE 1 (Anticipated Start Date September 17th – End Date Late October)

- Complete Deep Marsh Excavation between Pioneer Rd. and CTY E
- Detour WIS 164 for up to 30 days (CTY Q to CTY E)

2019

STAGE 2 (Anticipated Start Date – Late March)

- Begin construction - south project limits to WIS 167 (Holy Hill Rd.)
- Detour WIS 164 (CTY Q to CTY E)

STAGE 3 (Start Date Early June – End Date Late August)

- Continue construction - south project limits to WIS 167
- Construction of Roundabout WIS 164/WIS 167
- Close and Detour WIS 167 - Early June through Late August
- Continue Detour of WIS 164 (CTY Q to CTY E)
- COMPLETE ALL STAGE 2/3 WORK PRIOR TO SEPTEMBER 2019

STAGE 4 (Start Date Early June – End Date – Late October)

- Construction WIS 167 to CTY E
- Detour WIS 164 (CTY Q to CTY E)

PROJECT COMPLETION – LATE OCTOBER



For additional information about the project, contact:

WisDOT Project Manager
Kurt Flierl, P.E.
(414) 750-3085
Kurt.Flierl@dot.wi.gov

WisDOT Project Engineer
Ryan Schnurer
(414)-303-0029
Ryan.Schnurer@dot.wi.gov

WisDOT Project Engineer
Andrew Freund, P.E.
WisDOT Project Engineer
(414) 507-1867
Andrew.Freund@dot.wi.gov

WisDOT Const. Supervisor
Adrian Lopez, P.E.
(414) 750-1562
Adrian.Lopez@dot.wi.gov

