

# Wyocena - Montello (WIS 16 TO North County Line)

Summer 2020

## WIS 22, Columbia County



### **Project Location**

The roadway improvement project of WIS 22 begins north of the WIS 16 interchange in the Town of Wyocena and extends to the Columbia/Marquette County Line in the Town of Marcellon. The total project length is approximately 11 miles. *(See reverse side for a project location map.)*

### **Project Need**

The proposed project is needed to improve the existing deteriorating pavement surface and replace a structure over the Fox River that has exceeded its service life.

### **Proposed Improvements**

The proposed roadway improvements include milling the existing asphalt pavement and overlaying the entire roadway width with 4 inches of Hot Mix Asphalt (HMA). The proposed typical section for WIS 22 consists of one 12-foot travel lane in each direction with a 6-foot-wide shoulder (5-foot paved) on the left- and right-hand sides for the rural sections south of Pardeeville, and one 12-foot travel lane in each direction with a 6-foot-wide shoulder (6-foot paved) on the left- and right-hand sides for the rural section north of Pardeeville.

Additional WIS 22 roadway improvements include the following:

- Replacing box culvert B-11-0007 over the Fox River.
- Lining culvert C-11-3027.
- Resizing culvert C-11-2001.
- Upgrading sidewalk curb ramps to ADA compliance.
- Replacing existing guardrail to meet current standards.
- Replacing existing pavement markings.
- Replacing existing flashing beacons at the WIS 22 / WIS 33 intersection.

Temporary easements have been acquired for curb ramp improvements. No other real estate will be purchased for this project.

### **Construction Schedule / Traffic Impacts**

The project is currently scheduled to begin construction June 15<sup>th</sup>, 2020. The project will be completed in late September or early October depending on weather impacts.

Pavement replacement portions of the project will be completed open to traffic, using single lane closures with flagging operations. Minor delays for traffic will occur.

To complete replacement of the bridge over the Fox River, WIS 22 will be closed to through traffic with a detour posted. WIS 22 will be detoured onto WIS 44 and WIS 33 from mid-June to early September *(See reverse side for a detour location map)*. Access for residents, businesses, and emergency services will be maintained at all times during the project.

**For additional information  
about the project, contact:**

**Gregory Payne, P.E.**  
WisDOT Project Manager  
WisDOT, Southwest Region  
(608) 242-8058  
gregory.payne@dot.wi.gov

**Mike Novey, P.E.**  
Construction Project Engineer  
DAAR Engineering  
(608) 334-5215  
Mike.novey@daarcop.com

# Project Location Map

## WIS 22, Columbia County

